

200 Griffin Road, Unit 3, Portsmouth, NH 03801 Phone (603) 430-9282 Fax 436-2315

23 May 2023

Jason Garnham, Director of Planning and Development Town of Kittery 200 Rogers Road, Kittery, ME 03904

#### Re: Preliminary Site Plan Review Application; Conversion to Residential Tax Map 1, Lot 32, 35 Badgers Island West <u>Response to CMA Comments</u>

Dear Jason:

On behalf of BIW Inc. we hereby submitted revised plans and supporting material for **Preliminary Site Plan Review Approval** to address the comments from the May 18, 2023, review letter from CMA Engineers. The review was of our April 6, 2023, submission. The Planning Board, at your April 27, 2023, meeting, voted to schedule a Public Hearing for the May 25, 2023, Planning Board. The comments were just received on May 18<sup>th</sup>. While we understand there is limited time to review our response prior to the meeting, we would like the opportunity to walk the Board through our response at the meeting. The specific comments, repeated below with our responses in bold text, are as follows:

#### Cover

1. The legend should be updated to apply to the plans. We have edited the Legend to be site specific.

#### Sheet C1 – Existing Conditions Plan

1. The legend should be updated to apply to the plans. We have edited the Legend to be site specific. Is the Devegetated Coverage Calculation necessary on this sheet? We would like to leave it on as it provides added information about the existing site condition.

#### Sheet C2 - Shoreland Development Plan

1. It is not clear why the proposed building and driveway need to encroach into the wetland buffer. The project proposes minor intrusions into the wetland buffer and includes a reduction in the total buffer impact. The placement of the existing building on the property and the desire to revise the surface parking to underground parking create the need to impact the buffer to accomplish the project goals.

L-1 – Conceptual Landscape Plan

1. The proposed building configuration including driveways and walkways is different than what is shown on the plans. How does this change the landscape plan? The landscape plan will be revised to the current site layout and Ironwood comments addressed.

Sheet C3 – Utility Plan

- 1. The leader "Sewer Line to be Relocated" is confusing because it shows the existing and proposed sewer with leaders to both without a clear difference in the line types. Call out the new service separately (with the pipe size, material, and slope). **Done.** Is the invert out of the manhole the same? **Yes.** There should be details, notes, etc. on abandoning the old penetration, reconfiguring the manhole invert trough, if necessary, etc. **Notes have been added to the plans in this regard.**
- 2. Callout the new underground service run. **Done.**
- 3. The leader "Re-Use Water and Sprinkler Services" points to one water service. What is the size? Noted on plan. Is there capacity for domestic use and fire suppression in this one service? There are 2 services, we will work with the water department to confirm adequacy. There will be a net deduction in fixtures with the building conversion, including the addition.
- 4. The location of the sewer cleanout should be shown on the plans. Added to the plan.

#### Sheet C4 – Grading Plan

- 1. What are the details of the proposed heated driveway? The heated driveway will be serviced by a heated zone from the building HVAC system, therefore this detail will be perfected once the building design goes to construction drawings, after site approval.
- 2. Provide details and notes on termination of the existing pipe out of DMH #1657 proposed to be reused for roof drains. **Plans have been updated.**

#### Sheet C5 – Demolition Plan

- 1. There is a leader indicating "Sewer Service to Remain" but Sheet C3 indicates it is to be relocated. **Noted to be REMOVED.**
- 2. The existing drainage pipe that is to be partially removed should be shown and called out to be removed on the plan. **Done.**
- 3. The plans indicate that the "Gas...Service to be Relocated" but it is not shown elsewhere on the plans. Gas service will be eliminated.
- The limit of demolition should be expanded to include new pipe connection to DMH 1657.
  Done.

#### <u>Sheet T1 – Turning Template</u>

 The applicant has provided a turning template for the existing roadway, but none for the proposed site redevelopment. Does the fire department require proof of on-site access? The Fire Department has not indicated a need to access the site in that way for firefighting.

#### Sheet C7 – Lighting Plan

1. The plan should provide lighting calculations (illuminance), fixture type, mounting height, etc. Once the building layout is determined, the final design will be accomplished, and the information will be provided.

#### D2 – Details

1. Provide a detail for trench patch in Badger's Island West. See Detail H on Sheet D3.

We have the following comments on the drainage analysis:

- 1. While the drainage analysis shows that a reduction in impervious surface, and therefore stormwater flows is achieved in the developed condition, we note that neither the existing or proposed piping, structures, trench drains, permeable pavers and other treatment devices are modeled. We note that the existing piping is 12", which is the minimum pipe size allowed by the Ordinances. The capacity of the system in its existing and proposed configuration should be analyzed. We believe the analysis, at this point, shows the general run-off reduction achieved with the impervious surface area improvements. The analysis will be re-run after the layout is confirmed and stormwater will be routed, and the analysis provided.
- 2. In the Executive Summary, the lot size is described as 104,634 +/- square-feet (2.402 acres) and listed as 58,985 square-feet (1.354 acres). The lot size is an incorrect term in the Executive Summary and should be corrected to say the "Study area of on-site and adjacent flows"... is 104,634 and the "included off-site" associated drainage area is 147,12... The drainage analysis wording will be corrected. The area that is modelled in the analysis is correct.
- 3. Below Table 2, the text indicates "A plan sheet detailing the subcatchments and direction of runoff are included in the Appendix." We note that there are two figures (pre and post development) attached to the body of the report. The reference below the table should be corrected to "The Drainage patterns are shown on the attached Subcatchment Plans".
- 4. A component of the stormwater design improvements is the use of a Jellyfish stormwater filter. There is no discussion on the filter, other than its location in the Pre- and Post-Development Drainage section and a mention in the conclusion. A discussion of the purpose and benefits of the practice would be useful. The April 6 submitted application package included an entire section devoted to information about the Jellyfish system, including how the system works, performance testing results, system configurations, Maine State DEP approval, and system maintenance. The application material proposes that as a part of the development proposal, the applicant is willing to install the Jellyfish Filter system on an existing untreated outfall which drains adjacent property, including the town road.
- 5. The proposed subcatchments plan should include CB1 and CB2. Those are shown as yellow circles on the plan and can be more specifically labelled.
- 6. Has the condition of the existing structures (namely DMH #1657) been assessed? What size is DMH #1657? Is there room in the structure for another pipe penetration? This will be reviewed, and a report issued for final approval, once the layout of the site is confirmed.
- 7. For the existing 12"CPP that is proposed to be reused for roof drains, there is a leader indicating "pipe to be removed." What portion of the pipe is to remain? See Demolition Plan clarification. How is it removed/terminated at DMH #1657? This will be reviewed for final approval to determine if replacement of the manhole is required. What is the proposed connection from the roof drain to the reused section of pipe? The connection proposed is a tee connection(s). A detail will be added.
- 8. DMH2 in the Drainage Structure Schedule on Sheet C4 is missing the invert in for P8. Added.
- 9. CB2 does not have an invert out in the Drainage Structure Schedule on Sheet C4. This has been shown (number was in the wrong column).
- 10. What size are the proposed roof drains? Please provide details. See Detail on Sheet D5.

- 11. The site plans include a permeable paver patio and walkway. Have test pits and/or infiltration tests been completed on the existing soils to assess infiltration capacity? The sites can be reviewed, and the information provided. In addition, there are no details provided for the permeable pavers (select materials, piping, etc.) Detail added to Sheet C2.
- 12. The source of the rainfall event amounts should be included. The rainfall information is attached and will be added to the revised Analysis.
- 13. The Inspection & Long-Term Maintenance Plan should indicate that reports are required to be submitted to Code Enforcement Officer by July 1. The report list the requirement as "annually", we can add the exact date to the revision.
- 14. Under the Permeable paver section in the Inspection & Long-Term Maintenance Plan, outlet structures and appurtenances are referenced. Please clarify. **The wording should read "Repair porous installations as necessary to maintain functionality".**
- 15. The Permeable Paver Long-Term Maintenance Sheet references permeable pavement. The "pavement" wording will be replaced with "surface".
- 16. Has the jellyfish filter been designed in accordance with the specifications in the January 21, 2015, letter from Maine DEP? Are there design calculations or a project specific certification of compliance? The specific design for this site will be provided after the layout is established.

We hope that the Board agrees that this project will be a benefit to the community, and the environment. We hope that the Planning Board can complete the review of the proposed buffer intrusions at the May meeting and take a vote, after public input, on the projects conformance to Section 16.3.2.14.E of the Kittery Code. We look forward to our in-person presentation at the Planning Board meeting. Thank you for your time and attention to this proposal.

Please contact me if you have any questions or concerns regarding this application.

Sincerely,

John R. Chagnon, PE Ambit Engineering – Haley Ward CC: Project Team

P:\NH\5010135-Hampshire\_Development\3050.72A-Badgers Island W.(35)-JRC\3050.72A Hampshire Development\2022 Site Permitting\Applications\Town of Kittery\Planning Board Letter 4-6-23.docx

## **Extreme Precipitation Tables**

#### Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Smoothing	Yes
State	New Hampshire
Location	
Longitude	70.755 degrees West
Latitude	43.082 degrees North
Elevation	0 feet
Date/Time	Mon, 25 Jul 2022 15:42:48 -0400

#### **Extreme Precipitation Estimates**

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.26	0.40	0.50	0.65	0.81	1.04	1yr	0.70	0.98	1.21	1.56	2.03	2.65	2.92	1yr	2.35	2.81	3.22	3.94	4.54	1yr
2yr	0.32	0.50	0.62	0.81	1.02	1.30	2yr	0.88	1.18	1.52	1.94	2.48	3.20	3.57	2yr	2.84	3.43	3.93	4.67	5.32	2yr
5yr	0.37	0.58	0.73	0.97	1.25	1.61	5yr	1.08	1.47	1.89	2.43	3.14	4.06	4.57	5yr	3.59	4.40	5.03	5.93	6.69	5yr
10yr	0.41	0.65	0.82	1.11	1.45	1.89	10yr	1.25	1.73	2.23	2.89	3.74	4.86	5.52	10yr	4.30	5.31	6.07	7.09	7.96	10yr
25yr	0.48	0.76	0.97	1.34	1.77	2.34	25yr	1.53	2.14	2.78	3.63	4.73	6.16	7.09	25yr	5.45	6.81	7.79	9.00	10.03	25yr
50yr	0.54	0.86	1.10	1.54	2.07	2.76	50yr	1.79	2.53	3.29	4.32	5.65	7.37	8.57	50yr	6.52	8.24	9.40	10.79	11.95	50yr
100yr	0.60	0.97	1.25	1.77	2.42	3.26	100yr	2.09	2.98	3.90	5.15	6.76	8.83	10.36	100yr	7.81	9.96	11.35	12.93	14.24	100yr
200yr	0.67	1.10	1.43	2.05	2.82	3.83	200yr	2.44	3.51	4.61	6.12	8.07	10.58	12.52	200yr	9.36	12.04	13.72	15.50	16.97	200yr
500yr	0.80	1.31	1.71	2.48	3.48	4.76	500yr	3.00	4.38	5.76	7.70	10.20	13.44	16.10	500yr	11.90	15.48	17.62	19.72	21.43	500yr

#### **Lower Confidence Limits**

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.23	0.36	0.44	0.59	0.73	0.88	1yr	0.63	0.86	0.93	1.33	1.68	2.23	2.47	1yr	1.98	2.38	2.86	3.19	3.89	1yr
2yr	0.31	0.49	0.60	0.81	1.00	1.19	2yr	0.86	1.16	1.37	1.82	2.34	3.05	3.44	2yr	2.70	3.31	3.82	4.54	5.08	2yr
5yr	0.35	0.54	0.67	0.92	1.17	1.40	5yr	1.01	1.37	1.61	2.12	2.73	3.78	4.17	5yr	3.34	4.01	4.71	5.52	6.22	5yr
10yr	0.38	0.59	0.73	1.02	1.32	1.60	10yr	1.14	1.56	1.80	2.39	3.06	4.36	4.84	10yr	3.86	4.65	5.42	6.39	7.17	10yr
25yr	0.44	0.67	0.83	1.18	1.56	1.90	25yr	1.35	1.86	2.10	2.75	3.53	4.71	5.86	25yr	4.17	5.63	6.61	7.75	8.64	25yr
50yr	0.48	0.73	0.91	1.31	1.76	2.16	50yr	1.52	2.12	2.34	3.07	3.92	5.32	6.75	50yr	4.71	6.50	7.67	8.99	9.97	50yr
100yr	0.53	0.81	1.01	1.46	2.00	2.47	100yr	1.73	2.41	2.62	3.41	4.34	5.98	7.79	100yr	5.30	7.49	8.89	10.43	11.50	100yr
200yr	0.59	0.89	1.12	1.63	2.27	2.81	200yr	1.96	2.75	2.93	3.78	4.78	6.71	8.97	200yr	5.93	8.63	10.30	12.13	13.29	200yr
500yr	0.68	1.01	1.31	1.90	2.70	3.36	500yr	2.33	3.28	3.41	4.31	5.43	7.80	10.82	500yr	6.90	10.41	12.52	14.82	16.09	500yr

#### **Upper Confidence Limits**

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
1yr	0.28	0.44	0.54	0.72	0.89	1.08	1yr	0.77	1.06	1.26	1.74	2.20	2.98	3.16	1yr	2.63	3.04	3.57	4.37	5.03	1yr
2yr	0.34	0.52	0.64	0.86	1.07	1.27	2yr	0.92	1.24	1.48	1.96	2.52	3.42	3.70	2yr	3.02	3.56	4.09	4.84	5.62	2yr
5yr	0.40	0.62	0.76	1.05	1.34	1.62	5yr	1.15	1.58	1.88	2.54	3.25	4.33	4.96	5yr	3.84	4.77	5.37	6.37	7.15	5yr
10yr	0.47	0.72	0.89	1.24	1.61	1.98	10yr	1.39	1.93	2.28	3.11	3.96	5.33	6.21	10yr	4.72	5.97	6.83	7.84	8.75	10yr
25yr	0.58	0.88	1.09	1.56	2.05	2.57	25yr	1.77	2.51	2.96	4.07	5.16	7.76	8.35	25yr	6.87	8.03	9.17	10.34	11.41	25yr
50yr	0.67	1.02	1.27	1.83	2.46	3.13	50yr	2.12	3.06	3.60	5.00	6.33	9.71	10.48	50yr	8.60	10.08	11.48	12.73	13.97	50yr
100yr	0.79	1.19	1.50	2.16	2.96	3.81	100yr	2.56	3.73	4.38	6.16	7.78	12.15	13.14	100yr	10.75	12.64	14.37	15.71	17.10	100yr
200yr	0.92	1.39	1.76	2.55	3.56	4.65	200yr	3.07	4.55	5.34	7.59	9.56	15.24	16.50	200yr	13.49	15.86	18.02	19.37	20.93	200yr
500yr	1.15	1.71	2.20	3.19	4.54	6.04	500yr	3.92	5.90	6.94	10.03	12.60	20.59	22.29	500yr	18.23	21.44	24.31	25.55	27.36	500yr



# **RESIDENTIAL CONVERSION 35 BADGERS ISLAND WEST** KITTERY, MAINE AMENDED SITE PLAN B.I.W. GROUP, LLC 41 INDUSTRIAL DRIVE, UNIT 20 PRELIMINARY PLAN APPLICATION

OWNER & APPLICANT: EXETER, N.H. 03833

## CIVIL ENGINEER & LAND SURVEYOR: AMBIT ENGINEERING, INC.

200 GRIFFIN ROAD, UNIT 3 PORTSMOUTH, N.H. 03801-7114 TEL: (603) 430-9282 FAX: (603) 436-2315

LANDSCAPE ARCHITECT: WOODBURN & COMPANY LANDSCAPE ARCHITECTURE 103 KENT PLACE NEWMARKET, N.H. 03857 TEL: (603) 659-5949

# INDEX OF SHEETS

- EXISTING CONDITIONS PLAN C1 C2 - SHORELAND DEVELOPMENT PLAN – LANDSCAPE PLAN L1 – UTILITY PLAN C3 C4 – GRADING PLAN C5 DEMOLITION PLAN C6 – PARKING PLAN Τ1 - TURNING TEMPLATE PLAN C7 - LIGHTING PLAN D1-D5 - DETAILS

**OWNER:** 


SIGNATURE

DATE

APPROVED BY THE KITTERY PLANNING BOARD


CHAIRMAN

DATE





LEGEND:



AMENDED SITE PLAN TAX MAP 1, LOT 32 **RESIDENTIAL CONVERSION 35 BADGERS ISLAND WEST** KITTERY, MAINE



WWW.HALEYWARD.COM


200 Griffin Road, Unit 3 Portsmouth, NH 03801 603.430.9282


#### PLAN SET SUBMITTAL DATE: 18 MAY 2023

3050.72


TAX MAP 1 LOT 32


River	(95) (	
50	Atlantic Atlantic	
Gasoline Gasoline		1) BADGERS LANDING CONDOMINIUM STANDARD BOUNDARY
Wentworth Acres		BADGERS ISLAND WEST, KITTERY, YORK COUNTY, MAINE
	Less Contraction	SURVEY, INC. DATED SEPTEMBER 17, 2002, FINAL REVISION /
	36 Freemans	DATE SEPTEMBER 30, 2002. Y.C.R.D. PLAN BOOK 581,
a the state of the	36 hristian contraction of the second	
	Bridge Nobles	2) LAND TITLE SURVEY WEATHERVANE LOBSTER – SEAFOODS, THORNERS LANE, BADGERS ISLAND, KITTERY
	Badger	MAINE. PREPARED BY CIVIL CONSULTANTS. DATED AUGUST
a construction of the second o		21, 1996, FINAL REVISION SEPTEMBER 20, 1996. Y.C.R.D. / PLAN BOOK 231/23.
	AVE S	
	SITE	AS BADGERS ISLAND WEST ON BADGERS ISLAND, KITTERY
	X	MAINE, FOR THE TOWN OF KITTERY, MAINE. PREPARED BY /
	Sreek.	REVISION DATE SEPTEMBER 15, 1995. Y.C.R.D. PLAN BOOK
		225/12.
LOCATION MAP	SCALE 1"=2,0	000' 4) BOUNDARY PLAN OF LAND, CHARLES & MARYANN D. / 💰
I F(	GEND:	INC. DATED MAY 17, 1982. Y.C.R.D. PLAN BOOK 118/37.
N/F	NOW OR FORMERLY	5) GAGNER / SEWARD PROPERTY LINE EVALUATION
RP	RECORD OF PROBATE	SURVEYED SITE PLAN, KITTERY, MAINE. PREPARED BY
YCRD	YORK COUNTY REGISTRY OF DEEDS	KIMBALL CHASE. DATED SEPTEMBER 16, 1987. Y.C.R.D.
$\left(\frac{11}{21}\right)$	MAP 11 / LOT 21	
	BOUNDARY BUILDING SETBACK	6) PLAN OF LOTS, BADGERS ISLAND, KITTERY, MAINE
MHW	MEAN HIGH WATER LINE	DURGIN, CIVIL ENGINEER. DATED APRIL 1936. Y.C.R.D. PLAN
MSL	MEAN SEA LEVEL	
	MEAN LOW WATER MEAN LOWER LOW WATER	
HAT	MAINE DEP HIGHEST ANNUAL TIDE LINE	
•-	UNDERGROUND ELECTRIC	
• •	OVERHEAD ELECTRIC/WIRES SEWER LINE	
G	GAS LINE	
D	STORM DRAIN	
W 100	WATER LINE	
97x3	SPOT ELEVATION	
0	IRON ROD/PIPE FOUND	
•	IRON ROD SET	PISCATAQUA RIVER
	EDGE OF PAVEMENT (EP)	(TIDAL)
	WOODS / TREE LINE	
ØØ GWE	UTILITY POLE (w/ GUY) METER (GAS, WATER, ELECTRIC)	LEGEND (CONTINUED)
TYP.	TYPICAL	L. ELEVATION / / /
LSA	LANDSCAPED AREA IN	
WGV	WATER GATE VALVE	
<del>- 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0 - 0</del>	SIGNS	
СРР	CONNOCATED I BASILO TILE	$\frac{1}{2}$ AIR CONDITIONER $\frac{1}{2}$
PVC	POLYVINYL CHLORIDE PIPE	
	CATCH BASIN	
	SEWER MANHOLE	
$\bigcirc$	DRAIN MANHOLE	MLW MIL
_		
DEVEGETATE	D COVERAGE	UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING
CALCULATIO	N (TO HAT LINE)	AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE
		RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS
STRUCTURE	EXISTING (S.F.)	SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.
MAIN STRUCTURE	5,922	
PAVEMENT	12,289	
GRAVEL AREAS	2,277	
RETAINING WALLS CONCRETE PADS/STEPS	957	REVE
REVETMENT	5392	SLOP
TOTAL	26,923	20' DOCKING & MOORING
LOT SIZE	54,883	SETBACK PER SEE Y.C.R.D. 4676/185
% LOT COVERAGE	49.1%	
PURSUANT TO CHAPTER 90 PARTS		
STANDARDS OF PRACTICE AS ADOF LICENSURE FOR PROFESSIONAL LA	ND SURVEYORS, THE FOLLOWING	EXTENDS TO FEDERAL CHANNEL
EXCEPTIONS TO PART 2 ARE NOTE A) NO SURVEY REPORT HAS BE	ED;	S8 <u>7</u> <sup>•</sup> 58 <sup>2</sup> 1 <sup>™</sup>
B) NO LAND DESCRIPTION HAS I	BEEN PREPARED.	
C) MONUMENTS HAVE NOT BEEN		
THIS SURVEY CONFORMS TO THE FOR PROFESSIONAL LAND SURVEY(		
OF PRACTICE, EFFECTIVE DATE APP NOTED ON THIS PLAN.		
ARCOL	A . A A ?	DIRECTION FROM BOL
JOHN R. CHAGNON, PLS #2276	S. ( 8 · 23 DATE	SEE Y.C.R
	DAIL	





SEWER STRUCTURE SCHEDULE											
STRUCTURE	PROP/EX	RIM	SIZE/TYPE	INVERT IN	INVERT OUT	DIRECTION					
SMH 217	EX	16.33	6" PVC	8.98		FROM W					
			6" PVC	8.88		FROMNW					
			8" PVC		8.83	TO SMH 21					
						• · · · · · · · · · · · · · · · · · · ·					







WWW.HALEYWARD.COM

200 Griffin Road, Unit 3 Portsmouth, NH 03801 603.430.9282

### NOTES:

PROPANE

TANK

PVr

D3

1) THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.


2) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.

3) CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL BMP's" PUBLISHED BY THE MAINE D.E.P. IN 2016.

4) TOTAL PROJECT DISTURBED AREA 41,535 S.F.


5) VERTICAL DATUM IS NAVD88. BASIS OF VERTICAL DATUM IS REDUNDANT RTN GNSS OBSERVATIONS.

# SITE DEVELOPMENT 35 BADGERS ISLAND WEST KITTERY, MAINE



8" PVC

-0---




FB 423 PG 1 3050.72 74


## **DEMOLITION NOTES:**


- A) THE LOCATIONS OF UNDERGROUND UTILITIES ARE APPROXIMATE AND THE LOCATIONS ARE NOT GUARANTEED BY THE OWNER OR THE DESIGNER. IT IS THE CONTRACTORS' RESPONSIBILITY TO LOCATE UTILITIES AND ANTICIPATE CONFLICTS. CONTRACTOR SHALL REPAIR EXISTING UTILITIES DAMAGED BY THEIR WORK AND RELOCATE EXISTING UTILITIES THAT ARE REQUIRED TO BE RELOCATED PRIOR TO COMMENCING ANY WORK IN THE IMPACTED AREA OF THE PROJECT.
- B) ALL MATERIALS SCHEDULED TO BE REMOVED SHALL BECOME THE PROPERTY OF THE CONTRACTORS UNLESS OTHERWISE SPECIFIED. THE CONTRACTOR SHALL DISPOSE OF ALL MATERIALS OFF-SITE IN ACCORDANCE WITH ALL FEDERAL, STATE, AND LOCAL REGULATIONS, ORDINANCES AND CODES. THE CONTRACTOR SHALL COORDINATE REMOVAL, RELOCATION, DISPOSAL, OR SALVAGE OF UTILITIES WITH THE OWNER AND APPROPRIATE UTILITY COMPANY.
- C) ANY EXISTING WORK OR PROPERTY DAMAGED OR DISRUPTED BY CONSTRUCTION/ DEMOLITION ACTIVITIES SHALL BE REPLACED OR REPAIRED TO THE ORIGINAL EXISTING CONDITIONS BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
- D) THE CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES AND CALL DIG SAFE AT LEAST 72 HOURS PRIOR TO THE COMMENCEMENT OF ANY DEMOLITION/CONSTRUCTION ACTIVITIES.
- E) SAWCUT AND REMOVE PAVEMENT ONE FOOT OFF PROPOSED EDGE OF PAVEMENT TRENCH IN AREAS WHERE PAVEMENT IS TO BE REMOVED.
- F) IT IS THE CONTRACTOR'S RESPONSIBILITY TO FAMILIARIZE THEMSELVES WITH THE CONDITIONS OF ALL THE PERMIT APPROVALS.
- G) THE CONTRACTOR SHALL OBTAIN AND PAY FOR ADDITIONAL CONSTRUCTION PERMITS, NOTICES AND FEES NECESSARY TO COMPLETE THE WORK AND ARRANGE FOR AND PAY FOR ANY INSPECTIONS AND APPROVALS FROM THE AUTHORITIES HAVING JURISDICTION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY ADDITIONAL AND OFF-SITE DISPOSAL OF MATERIALS REQUIRED TO COMPLETE THE WORK.
- H) THE CONTRACTOR SHALL REMOVE AND DISPOSE OF ALL EXISTING STRUCTURES, CONCRETE, UTILITIES, VEGETATION, PAVEMENT, AND CONTAMINATED SOIL WITHIN THE WORK LIMITS SHOWN UNLESS SPECIFICALLY IDENTIFIED TO REMAIN. ANY EXISTING DOMESTIC / IRRIGATION SERVICE WELLS IN THE PROJECT AREA IDENTIFIED DURING THE CONSTRUCTION AND NOT CALLED OUT ON THE PLANS SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER AND ENGINEER FOR PROPER CAPPING / RE-USE.
- I) ALL WORK WITHIN THE TOWN OF KITTERY RIGHT OF WAY SHALL BE COORDINATED WITH THE TOWN OF KITTERY DEPARTMENT OF PUBLIC WORKS (DPW).
- J) REMOVE TREES AND BRUSH AS REQUIRED FOR COMPLETION OF WORK. CONTRACTOR SHALL GRUB AND REMOVE ALL STUMPS WITHIN LIMITS OF WORK AND DISPOSE OF OFF-SITE IN ACCORDANCE WITH FEDERAL, STATE, AND LOCAL LAWS AND REGULATIONS.
- K) CONTRACTOR SHALL PROTECT ALL PROPERTY MONUMENTATION THROUGHOUT DEMOLITION AND CONSTRUCTION OPERATIONS. SHOULD ANY MONUMENTATION BE DISTURBED, THE CONTRACTOR SHALL EMPLOY A LAND SURVEYOR TO REPLACE THEM.
- L) PROVIDE INLET PROTECTION BARRIERS AT ALL CATCH BASINS WITHIN CONSTRUCTION LIMITS AND MAINTAIN FOR THE DURATION OF THE PROJECT. INLET PROTECTION BARRIERS SHALL BE HIGH FLOW SILT SACK BY ACF ENVIRONMENTAL OR APPROVED EQUAL. INSPECT BARRIERS WEEKLY AND AFTER EACH RAIN OF 0.25 INCHES OR GREATER. CONTRACTOR SHALL COMPLETE A MAINTENANCE INSPECTION REPORT AFTER EACH INSPECTION. SEDIMENT DEPOSITS SHALL BE REMOVED AFTER EACH STORM EVENT OR MORE OFTEN IF WARRANTED OR FABRIC BECOMES CLOGGED. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO THE START OF ANY CLEARING OR DEMOLITION ACTIVITIES.
- M) THE CONTRACTOR SHALL PAY ALL COSTS NECESSARY FOR TEMPORARY PARTITIONING, BARRICADING, FENCING, SECURITY AND SAFELY DEVICES REQUIRED FOR THE MAINTENANCE OF A CLEAN AND SAFE CONSTRUCTION SITE.
- N) ANY CONTAMINATED MATERIAL REMOVED DURING THE COURSE OF THE WORK WILL REQUIRE HANDLING IN ACCORDANCE WITH MEDEP REGULATIONS. CONTRACTOR SHALL HAVE A HEALTH AND SAFETY PLAN IN PLACE, AND COMPLY WITH ALL APPLICABLE PERMITS, APPROVALS, AUTHORIZATIONS, AND REGULATIONS


PISCATAQUA RIVER (TIDAL)

MIN M










3.4.Hamnchire Develorment 2050 724-Radnere Island W (24)-IBC 2064 Hamnchire Develorment 2023 Cite Develorment 2023 Cite Develorment 2064 Truvico Tomorite 2023 NEW due 1/6/2023 2:06:42 PM Protocorde Protocorde



H\5010135.Hampshire\_Development\3050,72A.Badgers Island W (35)-JRC(3050,72A Hampshire Development\2022 Site Permitting/Plans & Specs/Site\3050,72A Site NEW 2022.dwg. 4/6/

## EROSION CONTROL NOTES

#### CONSTRUCTION SEQUENCE

DO NOT BEGIN CONSTRUCTION UNTIL ALL LOCAL, STATE, AND FEDERAL PERMITS HAVE BEEN APPLIED FOR AND RECEIVED.

INSTALL PERIMETER CONTROLS, i.e., SILT FENCING OR SILTSOXX AROUND THE LIMITS OF DISTURBANCE BEFORE ANY EARTH MOVING OPERATIONS. THE USE OF HAY BALES IS NOT ALLOWED.

CONSTRUCT STABILIZED CONSTRUCTION ENTRANCE.

PERFORM CLEARING & GRUBBING

CUT AND GRUB ALL TREES, SHRUBS, SAPLINGS, BRUSH, VINES AND REMOVE OTHER DEBRIS AND RUBBISH AS REQUIRED.

REMOVE PAVEMENT AS NEEDED.

BULLDOZE TOPSOIL INTO STOCKPILES, AND CIRCLE WITH SILT FENCING OR SILTSOXX. IF EROSION IS EXCESSIVE. THEN COVER WITH MULCH

ROUGH GRADE SITE. IN LANDSCAPED AREAS OUT OF THE WAY OF SUBSEQUENT CONSTRUCTION ACTIVITY, INSTALL TOPSOIL, MULCH, SEED AND FERTILIZE. STABILIZE PER DETAILS. CONSTRUCT FOUNDATIONS.

LAYOUT AND INSTALL ALL BURIED UTILITIES AND SERVICES TO THE PROPOSED BUILDING FOUNDATIONS. CAP AND MARK TERMINATIONS OR LOG SWING TIES.

CONSTRUCT BUILDING FRAMES.

FINISH GRADE SITE, DRIVEWAY & PARKING SUBBASE GRAVEL IN TWO, COMPACTED LIFTS. PROVIDE TEMPORARY EROSION PROTECTION TO DITCHES AND SWALES IN THE FORM OF MULCHING. JUTE MESH OR DITCH DAMS. CONSTRUCT BINDER COURSE.

BUILDING EXTERIOR WORK & LIGHT FIXTURES.

AFTER BUILDING IS COMPLETED FINISH ALL REMAINING LANDSCAPED WORK

CONSTRUCT ASPHALT WEARING COURSE.

REMOVE TRAPPED SEDIMENTS FROM COLLECTION DEVICES AS APPROPRIATE, AND THEN REMOVE TEMPORARY EROSION CONTROL MEASURES UPON COMPLETION OF FINAL STABILIZATION OF THE SITE.

#### GENERAL CONSTRUCTION NOTES

THE EROSION CONTROL PROCEDURES SHALL CONFORM TO "MAINE EROSION AND SEDIMENT CONTROL BMP's" PUBLISHED BY THE MAINE D.E.P. IN 2016.

DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED. THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED AT ANY ONE TIME DURING CONSTRUCTION, BUT IN NO CASE SHALL EXCEED 5 ACRES AT ANY ONE TIME BEFORE DISTURBED AREAS ARE STABILIZED.

AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED;

- A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; • A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED: OR.
- EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

ANY DISTURBED AREAS WHICH ARE TO BE LEFT TEMPORARILY, AND WHICH WILL BE REGRADED LATER DURING CONSTRUCTION SHALL BE MACHINE HAY MULCHED AND SEEDED WITH RYE GRASS TO PREVENT EROSION.

DUST CONTROL: IF TEMPORARY STABILIZATION PRACTICES, SUCH AS TEMPORARY VEGETATION AND MULCHING. DO NOT ADEQUATELY REDUCE DUST GENERATION, APPLICATION OF WATER OR CALCIUM CHLORIDE SHALL BE APPLIED IN ACCORDANCE WITH BEST MANAGEMENT PRACTICES.

ALL EROSION CONTROLS SHALL BE INSPECTED WEEKLY DURING THE LIFE OF THE PROJECT AND AFTER EACH STORM OF 0.5" OR GREATER. ALL DAMAGED SILT FENCES SHALL BE REPAIRED. SEDIMENT DEPOSITS SHALL PERIODICALLY BE REMOVED AND DISPOSED IN A SECURED LOCATION.

AVOID THE USE OF FUTURE OPEN SPACES (LOAM AND SEED AREAS) WHEREVER POSSIBLE DURING CONSTRUCTION. CONSTRUCTION TRAFFIC SHALL USE THE ROADBEDS OF FUTURE ACCESS DRIVES AND PARKING AREAS.

TOPSOIL REQUIRED FOR THE ESTABLISHMENT OF VEGETATION SHALL BE STOCKPILED IN AMOUNTS ALL PROPOSED VEGETATED AREAS WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH NECESSARY TO COMPLETE FINISHED GRADING OF ALL EXPOSED AREAS. CONSTRUCT SILT FENCE AROUND TOPSOIL STOCKPILE

AREAS TO BE FILLED SHALL BE CLEARED, GRUBBED AND STRIPPED OF TOPSOIL TO REMOVE TREES, VEGETATION, ROOTS OR OTHER OBJECTIONABLE MATERIAL. STUMPS SHALL BE DISPOSED BY GRINDING OR FILL IN AN APPROVED FACILITY.

ALL FILLS SHALL BE PLACED AND COMPACTED TO REDUCE EROSION, SLIPPAGE, SETTLEMENT, SUBSIDENCE OR OTHER RELATED PROBLEMS.

ALL FILL SHALL BE PLACED AND COMPACTED IN LAYERS NOT EXCEEDING 8 INCHES IN THICKNESS CONDITIONS. UNLESS OTHERWISE NOTED

INCORPORATED INTO FILLS.

FILL MATERIAL SHALL NOT BE PLACED ON FROZEN FOUNDATION SUBGRADE.

DISTURBED AREAS SHALL BE SEEDED WITHIN 72 HOURS FOLLOWING FINISHED GRADING

FROZEN MATERIAL OR SOFT, MUCKY OR HIGHLY COMPRESSIBLE MATERIAL SHALL NOT BE

AT NO TIME SHALL ANY DISTURBED AREA REMAIN UNSTABILIZED FOR LONGER THAN 72 HOURS. ALL AREAS WHERE CONSTRUCTION IS NOT COMPLETE WITHIN THIRTY DAYS OF THE INITIAL DISTURBANCE SHALL BE MACHINE HAY MULCHED AND SEEDED WITH RYE GRASS TO PREVENT FROSION

#### VEGETATIVE PRACTICE

FOR PERMANENT MEASURES AND PLANTINGS:

LIMESTONE SHALL BE THOROUGHLY INCORPORATED INTO THE LOAM LAYER AT A RATE OF 2 TONS PER ACRE.

FERTILIZER SHALL BE SPREAD ON THE TOP LAYER OF LOAM AND WORKED INTO THE SURFACE. FERTILIZER APPLICATION RATE SHALL BE 500 POUNDS PER ACRE OF 10-20-20 FERTILIZER.

SEED SHALL BE SOWN AT THE RATES SHOWN IN THE TABLE BELOW. IMMEDIATELY BEFORE SEEDING, THE SOIL SHALL BE LIGHTLY RAKED. ONE HALF THE SEED SHALL BE SOWN IN ONE DIRECTION AND THE OTHER HALF AT RIGHT ANGLES TO THE ORIGINAL DIRECTION. IT SHALL BE LIGHTLY RAKED INTO THE SOIL TO A DEPTH NOT OVER 1/4 INCH AND ROLLED WITH A HAND ROLLER WEIGHING NOT OVER 100 POUNDS PER LINEAR FOOT OF WIDTH. HAY MULCH SHALL BE APPLIED IMMEDIATELY AFTFR SEEDING AT A RATE OF 1.5 TO 2 TONS PER ACRE, AND SHALL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE EROSION AND SEDIMENT CONTROL HANDBOOK.

THE SURFACE SHALL BE WATERED AND KEPT MOIST WITH A FINE SPRAY AS REQUIRED, WITHOUT WASHING AWAY THE SOIL. UNTIL THE GRASS IS WELL ESTABLISHED. ANY AREAS WHICH ARE NOT SATISFACTORILY COVERED SHALL BE RESEEDED, AND ALL NOXIOUS WEEDS REMOVED.

A GRASS SEED MIXTURE CONTAINING THE FOLLOWING SEED REQUIREMENTS SHALL BE: GENERAL COVER PROPORTION SEEDING RATE

CREEPING RED FESCUE	50%	100 LBS/ACRE
		TOO LOO/MORE
KENTUCKY BLUEGRASS	50%	

<u>SLOPE SEED</u> (USED ON	ALL SLOPES (	GREATER THAN OR EQUAL T	0 3:1)
CREEPING RED FESCUE	42%	48 LBS /ACRE	

ALL FESCUE 48 LBS/ACRE BIRDSFOOT TREFOIL 16%

IN NO CASE SHALL THE WEED CONTENT EXCEED ONE PERCENT BY WEIGHT. ALL SEED SHALL COMPLY WITH APPLICABLE STATE AND FEDERAL SEED LAWS. FOR TEMPORARY PROTECTION OF DISTURBED AREAS:

MULCHING AND SEEDING SHALL BE APPLIED AT THE FOLLOWING RATES: PERENNIAL RYE: 0.7 LBS/1,000 S.F. MULCH: 1.5 TONS/ACRE

#### MAINTENANCE AND PROTECTION

THE CONTRACTOR SHALL MAINTAIN ALL LOAM & SEED AREAS UNTIL FINAL ACCEPTANCE AT THE COMPLETION OF THE CONTRACT. MAINTENANCE SHALL INCLUDE WATERING, WEEDING, REMOVAL OF STONES AND OTHER FOREIGN OBJECTS OVER 1/2 INCHES IN DIAMETER WHICH MAY APPEAR AND THE FIRST TWO (2) CUTTINGS OF GRASS NO CLOSER THEN TEN (10) DAYS APART. THE FIRST CUTTING SHALL BE ACCOMPLISHED WHEN THE GRASS IS FROM 2 1/2 TO 3 INCHES HIGH. ALL BARE AND DEAD SPOTS WHICH BECOME APPARENT SHALL BE PROPERLY PREPARED, LIMED AND FERTILIZED, AND RESEEDED BY THE CONTRACTOR AT HIS EXPENSE AS MANY TIMES AS NECESSARY TO SECURE GOOD GROWTH. THE ENTIRE AREA SHALL BE MAINTAINED, WATERED AND CUT UNTIL ACCEPTANCE OF THE LAWN BY THE OWNER'S REPRESENTATIVE.

THE CONTRACTOR SHALL TAKE WHATEVER MEASURES ARE NECESSARY TO PROTECT THE GRASS WHILE IT IS DEVELOPING

TO BE ACCEPTABLE, SEEDED AREAS SHALL CONSIST OF A UNIFORM STAND OF AT LEAST 90 PERCENT ESTABLISHED PERMANENT GRASS SPECIES, WITH UNIFORM COUNT OF AT LEAST 100 PLANTS PER SQUARE FOOT

SEEDED AREAS WILL BE FERTILIZED AND RESEEDED AS NECESSARY TO INSURE VEGETATIVE ESTABLISHMENT.

THE SWALES WILL BE CHECKED WEEKLY AND REPAIRED WHEN NECESSARY UNTIL ADEQUATE VEGETATION IS ESTABLISHED.

THE SILT FENCE BARRIER SHALL BE CHECKED AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL

SILT FENCING SHALL BE REMOVED ONCE VEGETATION IS ESTABLISHED, AND DISTURBED AREAS RESULTING FROM SILT FENCE REMOVAL SHALL BE PERMANENTLY SEEDED.


### <u>VINTER NOTES</u>

BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED BY SEEDING AND INSTALLING EROSION CONTROL BLANKETS ON SLOPES GREATER THAN 3:1, AND SEEDING AND PLACING 3 TO 4 TONS OF MULCH PER ACRE, SECURED WITH ANCHORED NETTING, ELSEWHERE. THE INSTALLATION OF EROSION CONTROL BLANKETS OR MULCH AND NETTING SHALL NOT OCCUR OVER ACCUMULATED SNOW OR ON FROZEN GROUND AND SHALL BE COMPLETED IN ADVANCE OF THAW OR SPRING MELT EVENTS

ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATIVE GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER OCTOBER 15TH, SHALL BE STABILIZED TEMPORARILY WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW


AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED





FB 423 PG 1

-3050.72





# AMBIT ENGINEERING, INC.

A DIVISION OF HALEY WARD, INĆ.

200 Griffin Road, Unit 3 Portsmouth, NH 03801 603.430.9282

WWW.HALEYWARD.COM


#### NOTES:

1) THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.

2) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.


3) CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL BMP's" PUBLISHED BY THE MAINE D.E.P. IN 2016.

# SITE REDEVELOPMENT 35 BADGERS ISLAND WEST KITTERY, ME



FB 423 PG 1

3050.72




SIZES

APPROVED 8" THROUGH 15" (SDR 35) 18" THROUGH 27" (T-1 & T-2) 4" THROUGH 18" (T-1 To T-3) 8" THROUGH 36" 8" THROUGH 15"

2. JOINT SEALS FOR PVC PIPE SHALL BE OIL RESISTANT COMPRESSION RINGS OF ELASTOMERIC MATERIAL CONFORMING TO ASTM D-3212 AND SHALL BE PUSH-ON BELL AND SPIGOT TYPE ABS TRUSS PIPE AND FITTINGS SHALL CONFORM TO ASTM D-2680. POLYMER COMPOUNDING

A21.11 RUBBER GASKET JOINTS FOR CAST IRON PRESSURE PIPE & FITTINGS.





WWW.HALEYWARD.COM

200 Griffin Road, Unit 3 Portsmouth, NH 03801 603.430.9282


NOTES:


1) THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.

2) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.

3) CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH THE "MAINE EROSION AND SEDIMENT CONTROL BMP's" PUBLISHED BY THE MAINE D.E.P. IN 2016.

# SITE REDEVELOPMENT 35 BADGERS ISLAND WEST KITTERY, ME







SCALE: AS SHOWN

FB 423 PG 1


DECEMBER 2022





## base-flow or seasonal flow, an upstream chemical spill or due to excessive sediment loading from site erosion or extreme runoff events. It is a good practice to inspect the system after major storm events. Inspection activities are typically conducted from surface observations and include: Observe if standing water is present • Observe if there is any physical damage to the deck or 3. Measure oil and sediment depth in several locations, by cartridge lids • Observe the amount of debris in the Maintenance Access Wall (MAW) or inlet bay for vault systems Maintenance activities include: • Removal of oil, floatable trash and debris Removal of collected sediments • Rinsing and re-installing the filter cartridges Replace filter cartridge tentacles, as needed Structure Inlet Pipe Maintenance Access Wall Downdrain Cartridge with Lid (outside of backwash pool) Cartridge Deck Sediment « Note: Separator Skirt not shown 2.0 Inspection Timing Inspection of the Jellyfish Filter is key in determining the maintenance requirements for, and to develop a history of, the site's pollutant loading characteristics. In general, inspections should be performed at the times indicated below; or per the approved project stormwater quality documents (if applicable), whichever is more frequent. 4. Collected rinse water is typically removed by vacuum hose. 5. Reassemble cartridges as detailed later in this document. Reuse O-rings and nuts, ensuring proper placement on each tentacle. **5.3 Sediment and Flotables Extraction** 1. Perform vacuum cleaning of the Jellyfish Filter only after

- filter cartridges have been removed from the system. Access the lower chamber for vacuum cleaning only through the maintenance access wall (MAW) opening. Be careful not to damage the flexible plastic separator skirt that is attached to the underside of the deck on manhole systems. Do not lower
- the vacuum wand through a cartridge receptacle, as damage to the receptacle will result. 2. Vacuum floatable trash, debris, and oil, from the MAW opening or inlet bay. Alternatively, floatable solids may be removed by a net or skimmer.



- 3. Pressure wash cartridge deck and receptacles to remove all sediment and debris. Sediment should be rinsed into the sump area. Take care not to flush rinse water into the outlet pipe.
- 4. Remove water from the sump area. Vacuum or pump equipment should only be introduced through the MAW or inlet bay. 5. Remove the sediment from the bottom of the unit through the



- **1.0 Inspection and Maintenance Overview**
- The primary purpose of the Jellyfish® Filter is to capture and remove pollutants from stormwater runoff. As with any filtration system, these pollutants must be removed to maintain the filter's maximum treatment performance. Regular inspection and maintenance are
- Maintenance frequencies and requirements are site specific and vary
- depending on pollutant loading. Additional maintenance activities Inspection is required immediately after an upstream oil, fuel or may be required in the event of non-storm event runoff, such as other chemical spill. 3.0 Inspection Procedure The following procedure is recommended when performing

- 4. Inspect cartridge lids. Missing or damaged cartridge lids to be replaced. 5. Inspect the MAW (where appropriate), cartridge deck and

Hi-Flo Cartrido

packwash pool

receptacles, and backwash pool weir, for damaged or broken components. 3.1 Dry weather inspections

oil layers

inspections:

- Inspect the cartridge deck for standing water, and/or sediment on the deck.
- No standing water under normal operating conditions. • Standing water inside the backwash pool, but not outside the backwash pool indicates, that the filter cartridges need to be rinsed.

A minimum of guarterly inspections during the first year of

accumulation, and to ensure proper functioning of the system.

inspection and maintenance plan developed in the first year of

operation to assess the sediment and floatable pollutant

Inspection frequency in subsequent years is based on the

operation. Minimum frequency should be once per year.

Inspection is recommended after each major storm event.

2. Inspect the MAW or inlet bay for floatable pollutants such as

lowering a sediment probe until contact is made with the floor

of the structure. Record sediment depth, and presences of any

1. Provide traffic control measures as necessary.

trash, debris, and oil sheen.



- For larger diameter Jellyfish Filter manholes ( $\geq$ 8-ft) and some vaults complete sediment removal may be facilitated by removing a cartridge lid from an empty receptacle and inserting a jetting wand (not a vacuum wand) through the receptacle. Use the sprayer to rinse loosened sediment toward the vacuum hose in the MAW opening, being careful not to damage the receptacle.
- 5.4 Filter Cartridge Reinstallation and Replacement Cartridges should be installed after the deck has been cleaned.
- It is important that the receptacle surfaces be free from grit and Remove cartridge lid from deck and carefully lower the filter
- cartridge into the receptacle until head plate gasket is seated squarely in receptacle. Caution: Do not force the cartridge downward; damage may occur.
- Replace the cartridge lid and check to see that both male threads are properly seated before rotating approximately 1/3 of a full rotation until firmly seated. Use of an approved rim gasket lubricant may facilitate installation. See next page for additional details.
- If rinsing is ineffective in removing sediment from the tentacles, or if tentacles are damaged, provisions must be made to replace the spent or damaged tentacles with new tentacles. Contact Contech to order replacement tentacles.

## 5.5 Chemical Spills

Caution: If a chemical spill has been captured, do not attempt naintenance. Immediately contact the local hazard response gency and contact Contech.

The accumulated sediment found in stormwater treatment and

#### 5.6 Material Disposal

conveyance systems must be handled and disposed of in accordance with regulatory protocols. It is possible for sediments to contain measurable concentrations of heavy metals and organic chemicals (such as pesticides and petroleum products). Areas with the greatest potential for high pollutant loading include industrial areas and heavily traveled roads. Sediments and water must be disposed of in accordance with all applicable waste disposal regulations. When scheduling maintenance, consideration must be made for the disposal of solid and liquid wastes. This typically requires coordination with a local landfill for solid waste disposal. For liquid waste disposal a number of options are available including a municipal vacuum truck decant facility, local waste water treatment plant or on-site treatment and discharge.

- Standing water outside the backwash pool is not anticipated and may indicate a backwater condition caused by high water elevation in the receiving water body, or possibly a blockage in downstream
- infrastructure. • Any appreciable sediment ( $\geq 1/16''$ ) accumulated on the deck surface should be removed.
- 3.2 Wet weather inspections
  - Observe the rate and movement of water in the unit. Note the depth of water above deck elevation within the MAW or inlet bay. • Less than 6 inches, flow should be exiting the cartridge
  - lids of each of the draindown cartridges (i.e. cartridges located outside the backwash pool). Greater than 6 inches, flow should be exiting the
  - cartridge lids of each of the draindown cartridges and each of the hi-flo cartridges (i.e. cartridges located inside the backwash pool), and water should be overflowing the backwash pool weir. • 18 inches or greater and relatively little flow is exiting
- the cartridge lids and outlet pipe, this condition indicates that the filter cartridges need to be rinsed.

#### 4.0 Maintenance Requirements

Required maintenance for the Jellyfish Filter is based upon results of the most recent inspection, historical maintenance records, or the site specific water quality management plan; whichever is more frequent. In general, maintenance requires some combination of the following:

- 1. Sediment removal for depths reaching 12 inches or greater, or within 3 years of the most recent sediment cleaning, whichever occurs sooner.
- 2. Floatable trash, debris, and oil removal.
- 3. Deck cleaned and free from sediment.
- 4. Filter cartridges rinsed and re-installed as required by the most recent inspection results, or within 12 months of the most recent filter rinsing, whichever occurs sooner.
- Replace tentacles if rinsing does not restore adequate hydraulic capacity, remove accumulated sediment, or if damaged or missing. It is recommended that tentacles should remain in service no longer than 5 years before replacement.
- 6. Damaged or missing cartridge deck components must be repaired or replaced as indicated by results of the most recent inspection.
- 7. The unit must be cleaned out and filter cartridges inspected immediately after an upstream oil, fuel, or chemical spill. Filter cartridge tentacles should be replaced if damaged or compromised by the spill.

#### 5.0 Maintenance Procedure The following procedures are recommended when maintaining the Jellyfish Filter:

- Provide traffic control measures as necessary.
- 2. Open all covers and hatches. Use ventilation equipment as required, according to confined space entry procedures. Caution: Dropping objects onto the cartridge deck may cause damage.


- Perform Inspection Procedure prior to maintenance activity.
- To access the cartridge deck for filter cartridge service, descend into the structure and step directly onto the deck. Caution: Do not step onto the maintenance access wall (MAW) or backwash pool weir, as damage may result. Note that the cartridge deck may be slippery.
- 5. Maximum weight of maintenance crew and equipment on the cartridge deck not to exceed 450 lbs.

#### 5.1 Filter Cartridge Removal

- Remove a cartridge lid.
- Remove cartridges from the deck using the lifting loops in the cartridge head plate. Rope or a lifting device (available from Contech) should be used. Caution: Should a snag occur, do not force the cartridge upward as damage to the tentacles may result. Wet cartridges typically weigh between 100 and 125 lbs.
- Replace and secure the cartridge lid on the exposed empty receptacle as a safety precaution. Contech does not recommend exposing more than one empty cartridge receptacle at a time.


#### 5.2 Filter Cartridge Rinsing

1. Remove all 11 tentacles from the cartridge head plate. Take care not to lose or damage the O-ring seal as well as the plastic threaded nut and connector.




- 2. Position tentacles in a container (or over the MAW), with the threaded connector (open end) facing down, so rinse water is flushed through the membrane and captured in the container.
- 3. Using the Jellyfish rinse tool (available from Contech) or a low-pressure garden hose sprayer, direct water spray onto the tentacle membrane, sweeping from top to bottom along the length of the tentacle. Rinse until all sediment is removed from the membrane. Caution: Do not use a high pressure sprayer or focused stream of water on the membrane. Excessive water pressure may damage the membrane.





AMBIT E	DF HALEY WARD, IN	<b>i, INC.</b> c. <b>~~</b>
WWW.HALEYWARD.COM	Portsm	iffin Road, Unit 3 outh, NH 03801 0.9282
· ·	NOTIFY DIG SAFE AT 1888- T 72 HOURS PRIOR TO COMM PRIVATE PROPERTY.	
AVAILABLE EVIDENCE AND ARE PROTECTING ANY ABOVEGROU SOLE RESPONSIBILITY OF THE	OCATIONS ARE BASED UPON E NOT FIELD VERIFIED. LOCATI ND OR UNDERGROUND UTILITII CONTRACTOR AND/OR THE O E REPORTED AT ONCE TO TH	NG AND ES IS THE DWNER.
MEASURES IN ACCORDANCE W	ALL AND MAINTAIN EROSION ( /ITH THE ``MAINE EROSION AN BY THE MAINE D.E.P. IN 201	D SEDIMENT
SITE REDEV 35 BADGER KITTERY, M	S ISLAND	
	·······	
	AL RIPTION REVISIONS	1/19/23 DATE
	OF MANNEN HILL NOHN AGNON SUSED ENSED MAL ENGINITION MAL ENGINITIO	- 23
SCALE: AS SHOWN	DECEMBE	R 2022
FB 423 PG 1		



	A DIVISION OF HALEY WARD, INC.
	200 Griffin Road, Unit 3      Portsmouth, NH 03801      603.430.9282
	NOTES: 1) THE CONTRACTOR SHALL NOTIFY DIG SAFE AT 1-888-DIG-SAFE (1-888-344-7233) AT LEAST 72 HOURS PRIOR TO COMMENCING ANY EXCAVATION ON PUBLIC OR PRIVATE PROPERTY.
	2) UNDERGROUND UTILITY LOCATIONS ARE BASED UPON BEST AVAILABLE EVIDENCE AND ARE NOT FIELD VERIFIED. LOCATING AND PROTECTING ANY ABOVEGROUND OR UNDERGROUND UTILITIES IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/OR THE OWNER. UTILITY CONFLICTS SHOULD BE REPORTED AT ONCE TO THE DESIGN ENGINEER.
	3) CONTRACTOR SHALL INSTALL AND MAINTAIN EROSION CONTROL MEASURES IN ACCORDANCE WITH THE ''MAINE EROSION AND SEDIMENT CONTROL BMP's" PUBLISHED BY THE MAINE D.E.P. IN 2016.
	SITE REDEVELOPMENT 35 BADGERS ISLAND WEST KITTERY, ME
RIOR WALL SHEET METAL OR CAST IRON DOWNSPOUT O ROOF — PROVIDE STRAP FOR EACH ENGTH OF PIPE — SIZE AS REQUIRED	
/4" x 3/16" SHEET METAL STRAP – ANCHOR WALL WITH EXPANSION SHIELDS – PROTECT AP WITH ENAMEL PAINT, UNLESS GALVANIZED AP IS USED	1 DETAIL O 5/18/23
EANOUT "T" BRANCH WITH THREADED PLUG FINISH GRADE	0  ISSUED FOR APPROVAL  1/19/23    NO.  DESCRIPTION  DATE    REVISIONS
	STATE OF MAINE
CAST IRON SOIL PIPE OR PVC PIPE - SIZE VARIES AS REQUIRED	JOHN RGNON No 1950
CONNECT TO 6'Ø ROOF	5./8.23
DRAIN, SLOPE TO OUTLET © 0.01ft./ft. (MIN.)	SCALE: AS SHOWN DECEMBER 2022
WNSPOUT SHOE ROOF GUTTERS) NTS	DETAILS D5
	FB 423 PG 1 3050.72



May 24, 2023

Mr. Dutch Dunkelberger Chair Kittery Planning Board 200 Rogers Road Kittery, ME 03904

RE: 35 Badgers Island Landscape Plan – Peer Review Comments

Dear Chair Dunkelberger and Planning Board Members:

We are in receipt of Ironwood Design Group's landscape architecture peer review comments for the 35 Badger's Island development. We have updated our landscape plan and coordinated with Ambit's updated plans such that Ironwood's comments have been addressed.

#### Specifically:

**Item 1.** All items listed are now consistent between the landscape and civil drawings except for trees to be saved/removed. Landscape plan is current and civil plans will be coordinated in the next submission.

**Item 2.** The underground utilities have been accounted for and shown on the landscape plans, conflicts have been resolved.

**Item 3.** A dark sky compliant lighting plan with the required specifications will be developed and provided in subsequent submissions prior to completion of planning board review.

Item 4. Open Space information has been added to the Civil Plans.

Item 5. Plant list spelling correction has been completed.

**Item 6.** Perennials, including the Sedum 'Autumn Joy' called out by Ironwood are shown on the plan and are to be located in field by Landscape Architect per the plant list notes.

**Item 7.** Detail H/D3 in the civil package has been deleted in favor of the Tree Planting and Shrub Planting details on L-1.

a. Both shrubs and trees are to be planted on undisturbed or hand tamped existing soils, no additional soils to be used to avoid plant settlement.

103 KENT PLACE NEWMARKET, NH 03857 603.659.5949 woodburnandcompany.com



- b. Both the tree and shrub details call for all wire baskets to be removed.
- c. Tree detail calls for root flare to be set 2-3" above existing grade.

Item 8. Paver detail has been updated on civil plans.

Item 9. Detail has been updated on civil plans to be porous.

**Item 10.** Details requested will be provided in subsequent submissions prior to completion of planning board review.

#### Item 11.


- a. Detailed planting notes have been provided and are on L-1.
- b. Loam notes and specifications are part of the planting notes on L-1.
- c. Loam specification is addressed in planting notes on L-1.
- d. Driveways will be heated snow storage, if any, will be minimal.
- e. The area labeled "Existing plantings, keep and protect" along the northeast property line is shown in the photo below. These plants to remain and be protected will be added to civil plans for consistency in subsequent submissions.




103 KENT PLACE NEWMARKET, NH 03857 603.659.5949 woodburnandcompany.com

#### Landscape Notes

- 1. Design is based on drawings by Ambit Engineering. Drawings may require adjustment due to actual field conditions.
- 2. This plan is FOR REVIEW purposes ONLY, NOT for Construction. Construction Documents will be provided upon request.
- 3. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from erosion.
- 4. Erosion Control shall be in place prior to construction. 5. Erosion Control shall comply with State and Local Erosion &
- Sedimentation Control Practices 6. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in
- layout and/or grade relationships prior to construction. 7. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- 8. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line or at the distance in feet from the trunk equal to the diameter of the tree caliper in inches, whichever is greater, and shall be expanded to include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- 9. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
- 10. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 811 or 888-DIG-SAFE (1-888-344-7233.)
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall amend all soils to be used for lawns and plant beds per testing results' recommendations and review with Landscape Architect. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- 13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a Contractor is aware of a potential issue and does not bring it to the attention of the Landscape Architect or Owner's Representative immediately, they may be responsible for the labor and materials associated with correcting the problem.
- 14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 16. All plants shall be legibly tagged with proper botanical name.
- 17. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 18. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- 19. All landscaping shall be provided with the following:
- a. Outside hose attachments spaced a maximum of 150 feet apart, and
- b. An underground irrigation system, or
- c. A temporary irrigation system designed for a two-year period of plant establishment.
- 21. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
- 22. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, watering of plants, including
- seeding and weeding. Plants shall be appropriately watered prior to, during, and after planting. It is the Contractor's responsibility to provide clean water suitable for plant health from off site, should it not be available on site.
- 23. All disturbed areas will be dressed with 6" of loam and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- 24. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be black.
- 25. Drip strip shall extend to 6" min. beyond roof overhang and shall be edged with 3/16" thick metal edger.
- 26. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 27. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 8' to allow clear and safe passage of vehicles and pedestrians under tree canopy. Shrubs and ornamental plantings adjacent to vehicular travel way shall not exceed three feet in height where sightlines would be blocked. If pruning is necessary to maintain the required maximum height, plants PE shall be pruned to a natural form and shall not be sheared.
- 28. Snow shall be stored a minimum of 5' from shrubs and trunks of
- 29. The Landscape Contractor shall guarantee all lawns and plant materials for a period of not fewer than two years. Dead, dying, or diseased planting shall be removed and replaced within the growing season
- 30. Landscape Architect is not responsible for the means and methods of the Contractor.





TREES

mbol	Botanical Name	Common Name	Quantity	Size	
١m	Amelanchier grandiflora 'Robin Hill'	Robin Hill Serviceberry	5	8-10' ht	E
٩R	Acer rubrum 'October Glory'	October Glory Red Maple	6	3" cal.	
Ξx	Existing tree to remain	Existing tree to remain			
am	Hamamelis x 'Arnold Promis'	Arnold Promise Witch Hazel	2	7-8' ht.	F
JV	Juniperus virginiana ' Manhattan Blue'	Manhattan Blue Eastern Red Cedar	5	7-8' ht.	
/lal	Malus 'Tina'	Tina Crabapple	2	2.5" cal.	
lal2	Malus 'Sugartyme'	Sugar Tyme Crabapple	1	2.5" cal.	
QR	Quercus rubra	Northern Red Oak	2	3" cal	
JA	Ulmus americana 'Princeton'	Princeton Elm	3	3" cal	

#### SHRUBS


Symbol	Botanical Name	Common Name	Quantity	Size
CIH	Cornus 'Ivory Halo'	Ivory Halo Dogwood	12	2-5'3' ł
CL	Clethra alnifolia 'Hummingbird'	Hummingbird Clethra	258	3 gal
HY	Hydrangea macrophylla 'All Summer Beauty'	All Summer Beauty Hydrangea (Blue	5	3 gal
HY2	Hydrangea paniculata 'Little Quickfire'	Little Quickfire Panicle Hydrangea	10	5 gal
HYA	Hydrangea a. 'Incrediball'	Incrediball Hydrangea	34	5 gal
HyP	Hydrangea paniculata 'Limelight'	Limelight Hydrangea	4	10 ga
lg	llex glabra 'Shamrock'	Shamrock Inkberry	25	5 gal
Jc	Juniperus communis	Common Juniper	162	3 gal
MP	Myrica pennsylvanica	Bayberry	60	5 gal
RH	Rhododendron chionoides	Chioniodes Rhododendron	11	5 gal
Rh2	Rhododendron 'Wilsoni'	Wilson Rhododendron	10	3 ga
RHUS	Rhus aromatica 'Grow Low'	Grow Low Sumac	210	3 ga
Rv	Rosa virginiana	Virginia Rose	41	2.5-3
SP	Spirea latifolia "Pink Mountain'	Pink Mountain Spirea	96	3 gal
Tax	Taxus media 'Everlow'	Everlow Yew	25	3 ga

Symbol	Botanical Name	Common Name	Quantity	Size
Arc	Arctostaphylos uva-ursi	Bearberry	80	1 gal
CAL	Calamagrostis acutifolia 'Karl Foerster'	Feather Reed Grass	14	1 gal
DAY	Daylily mix	Mixed Daylilies	59	1 gal
SED	Sedum 'Autumn Joy'	Autumn Joy Sedum	14	1 gal
PENN	Pennisetum alopecuroides 'Hameln'	Hameln Dwarf Fountain Grass	14	1 gal

Comments BB min. 30" ht min. 30" ht min. 30" ht min. 30" ht treeform, min. 30" ht min. 18" ht./spread min. 18" ht./spread min. 30" ht min. 18" ht./spread min. 18" ht./spread min. 30" ht

min. 30" ht min. 18" ht./spread

Comments min. 2 yr clumps min. 2 yr clumps min. 2 yr clumps min. 2 yr clumps min. 2 yr clumps



South

(3)HyA -

(4)Jc


(3)HvA

(5)CIH

(82) CL


 $(4)H_1$ 

(4)Rh -



 $\Box$ 

Drawn By:	WSA
Checked B	y: RW
Scale:	1"=20'-0"
Date:	2023-05-25 for PB submission
Revisions:	submission



© 2023 Woodburn & Company Landscape Architecture, LLC